

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-10450-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 33-32S-2E
3664 feet from S Section Line, 1128 feet from E Section Line
Lease Name: LEE Well #: 3
County: SUMNER Total Vertical Depth: 3368 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>32679</u>	PROD	5.5	3368		200 SX
Op Name: <u>AAS OIL CO., INC.</u>	SURF	8.625	145		100 SX
Address: <u>2508 EDMONT DR STE # 4</u> <u>ARKANSAS CITY, KS 67005</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2017 12:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: _____ Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 10/12/2017 12:00 AM KCC Agent: DAN FOX

Actual Plugging Report:

RAN 2" TUBING TO 333'. PUMPED 45 SACKS 60/40 POZ 4% GEL 4% CC AND DISPLACED ON BOTTOM. PULLED TUBING OUT RAN IN HOLE WITH WIRELINE AND TAGGED CEMENT TOP @ 3131'. PERFORATED 5.5" CASING @ 300'. RAN 2" TUBING TO 320'. PUMPED 180 SXS 60/40 POZ 4% GEL 2% CC CIRCULATED CEMENT TO TOP OF CASING BUT LOST CIRCULATION UP SURFACE PIPE, SHUT DOWN LET CEMENT SET OVERNIGHT. NEXT DAY TAGGED CEMENT IN SURFACE PIPE @ 60' RAN 1" TUBING AND CIRCULATED CEMENT TO SURFACE. TAGGED CEMENT IN CASING @ 287'. RAN 1" TUBING TO 280' CIRCULATED CEMENT TO SURFACE.

Perfs:

INVOICED
JAN 8 0 2018

Remarks: COMPLIANCE TA NOV SENT ON 5-4-2017

Plugged through: TBG

District: 02

Signed Daniel R. Lee
(TECHNICIAN)