

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-097-21325-00-00
 Spot: NENWSESW Sec/Twnshp/Rge: 7-28S-17W
1214 feet from S Section Line, 3564 feet from E Section Line
 Lease Name: W V MCELWAIN Well #: ET UX 1
 County: KIOWA Total Vertical Depth: 4850 feet

Operator License No.: 6926
 Op Name: ADVANTAGE RESOURCES, INC.
 Address: 1775 SHERMAN ST STE 1700
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4700		WITH 2 SX CMT
PROD	4.5	4804	2430	WITH 195 SX CMT
SURF	8.625	473		WITH 260 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/18/2018 12:00 PM
 Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
 Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4700' WITH 2 SX CMT. PLUG AT 1130' WITH 10 SX GEL & 50 SX CMT. PLUG AT 510' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: PARTIAL
 Date/Time Plugging Completed: 01/18/2018 2:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4700' WITH 2 SX CMT. 1ST PLUG AT 1130' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 510' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED BUT FELL. TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4756	4780		

INVOICED

JAN 20 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed  (TECHNICIAN)

RECEIVED
 JAN 22 2018
 KCC DODGE CITY