

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20562-00-00
Spot: S2S2SW Sec/Twnshp/Rge: 5-16S-10W
330 feet from S Section Line, 3960 feet from E Section Line
Lease Name: OSHEL A Well #: 1
County: ELLSWORTH Total Vertical Depth: 3299 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3297		125 SX
SURF	8.625	312		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2017 12:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: _____ Phone: (620) 275-2963

Proposed Plugging Method: As Per District 2 Instructions

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/29/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Could not get down casing with tubing past 83 feet, would go outside casing to 118 feet. Brought in Mudd pump and Swivel with cone bit, and weighted drill pipe. Could get to bottom with weighted pipe but when try to get down with tubing or wireline would get stuck at 118', made several attempts to ream past tight area, with no success. Ran to 3234' with weighted pipe and pump 30 sks cement pull tbg to 1408' pump 35 sks cement, pull tubing to 1000' pumped 35 sks pull tbg to 350' circulated cement to surface w/ 30 sks pull out tbg hook-up to csg pump 70 sks cement, Next day tagged TOC at 43' filled with 10 sx of cement.

Perfs:

Top	Bot	Thru	Comments
3297	3299		

INVOICED
JAN 20 2018

Remarks: SWIFT SERVICES WAS THE CEMENT COMPANY ON LOCATION. PAST 10 YEAR TA

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)



1/5