

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,145-21,190.0000

LEASE NAME Saxton

WELL NUMBER #1

3960 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 29 TWP. 20 RGE. 20 (E) or (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 5-7-91

Plugging Completed 5-13-91

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John J. Darrah, Jr.

ADDRESS 412 E. Douglas, Suite #1, Wichita, Ks. 67202

PHONE# (316-263-2243) OPERATORS LICENSE NO. 5088

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 7, 1991 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1358'	None
				5-1/2"	4500'	1,432.51'

MAY 21 1991
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 4250' and 5 sacks cement. Shot casing at 3014', 2721', 2339', 2041', 1720' and 1421'. Pulled 36 jts. of 5-1/2" casing. Allied plugged well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, 8-5/8" plug and 150 sacks 60/40 pozmix with 6% gel. Maximum pressure was 1400 psi and shutin 800 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John J. Darrah, Jr.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well verified that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 20th day of May, 1991

Jana M. Leatherman
Notary Public

My Commission Expires: _____

