

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavits
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 29 Twp. 20S Rge. (E) 20W (W)

Location as "NE/CNW/SW" or footage from lines Cen SE NW

Lease Owner Lario Oil & Gas Company

Lease Name Saxton Well No. 1

Office Address 301 S. Market, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed January 8 19 54

Application for plugging filed December 14 19 65

Application for plugging approved December 15 19 65

Plugging commenced January 10 19 66

Plugging completed January 19 19 66

Reason for abandonment of well or producing formation Depleted - Uneconomical

If a producing well is abandoned, date of last production December 13 19 65

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker

Producing formation Mississippian Depth to top 4312 Bottom Total Depth of Well 4320 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	440	None
				5 1/2"	4335.48	set at
					4309 1/2	2446'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pulled pipe, put in 8 5/8" swedge, pumped into 8 5/8" pipe 35 sacks of mud and 100 sacks of cement to plug well.

Recovered 2446' of 5 1/2".

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address Box 156, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

G. R. Kelsey (employee of owner) or (owner/operating) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

301 S. Market, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN to before me this 27th day of January, 19 66

Frances Lealie

Notary Public.

My commission expires July 21, 1966

LARIO OIL & GAS COMPANY
 Edith Saxton No. 1
 Cen. SE NW Sec. 29-20S-20W
 Pawnee County, Kansas

Drilling Commenced: December 6, 1963
 Drilling Completed: December 22, 1963
 Well Completed: January 8, 1964
 Drilling Contractor: Gabbert-Jones, Inc.
 Total Depth = 4322'
 I.P. = 17 bbls. oil plus 247 bbls. water 24 hours

CASING RECORD:

8 5/8" 440' Set @ 450' Cem. 300 sacks
 5 1/2" 4335.48' Set @ 4309.52' Cem. w/
 100 sacks

<u>Formation</u>	<u>Depth</u>	<u>GEOLOGICAL TOPS - K.B. MEAS.</u>	
Clay	500	Elevation	2161' K.B.
Red bed	683		2156' Gr.
Anhydrite Blaine	692	Blaine Anhydrite	683' (+1478')
Sand and red bed	1165	Stone Corral Anhydrite	1344' (+ 817')
Red bed	1344	Heebner	3690' (=1529')
Anhydrite	1370	Lansing	3741' (=1580')
Shale	1570	Fort Scott	4240' (=2079')
Shale & lime	2150	Cherokee	4261' (=2100')
Lime	2365	Mississippian	4312' (=2151')
Shale & lime	3735	Rotary Total Depth	4322' (=2161')
Lime	3910		
Shale & lime	3980		
Lime (K.C.)	4080		
Shale & lime	4150		
Lime	4322		

12-28-63 Dowell acidized open hole w/ 500 gallons mud acid.
 12-28-63 Dowell treated w/ 1000 gallons kerosene, 5 gallons Freflo and
 2 gallons F33 flushed with oil.
 1-4-64 Dowell treated with 250 gallons aifapropal alcohol.
 1-6-64 Dowell treated w/ 500 gallons aifapropal alcohol, 500 gallons
 water treated w/ J111; 2500 gallons water treated w/ J111;
 2500# of 20-40 sand.

RECEIVED
 STATE CORPORATION COMMISSION

DEC 15 1965

CONSERVATION DIVISION
 Wichita, Kansas