


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 31 Twp. 20S Rge. ~~20~~ 20 (W)
Location as "NE/CNW&SW" or footage from lines C NE NE
Lease Owner Pickrell Drilling Company
Lease Name Patmon-Seelye "A" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Sept. 6 19 64
Application for plugging filed August 28 19 70
Application for plugging approved August 28 19 70
Plugging commenced August 29 19 70
Plugging completed Sept. 1 19 70
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production August 7 19 70
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Mississippian Osage Depth to top 434 Bottom 435 Total Depth of Well 4353 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1375'	None
				5-1/2"	4345'	3272'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

August 29, 1970 Plugged off bottom. Dumped sand to 4320'. Mixed and dumped 5 sx of cement to 4280'.
September 1, 1970 Plugged off top. Set 10' rock bridge, from 450' to 460'. Filled 8-5/8" surface casing, from 450' to base of cellar, with 6 yards of 3000 lb. test P.S.I. ready mix concrete.

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling, Inc.
Address P. O. Box 1082, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale M. Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale M. Robinson
705 Fourth National Bank Bldg, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 18th day of September, 19 70

My commission expires January 19, 1973
Esther Lamone
Notary Public.



ROTARY DRILLING LOG

Operator: Beardmore Drilling Company Contractor: Rains & Williamson
 No. 1 Patmon-Seelye Oil Co.
 Approx. C NE NE Sec. 31-20S-20W Commenced: 8-26-64
 Pawnee County, Kansas Completed: 9-6-64
 Remarks: Set 1375' 3-5/8" surface casing with 600 sacks common cement.
 Ran 5-1/2" casing, set with 75 sacks cement.

Formations

Surface Soil	5'
Clay & Post Rock	50'
Shale	165'
Sand	202'
Shale	630'
Red Bed	713'
Anhydrite	721'
Shale & Sand	770'
Sand	1010'
Red Bed & Shale	1370'
Anhydrite	1381'
Anhydrite	1397'
Shale & Shells	2085'
Lime & Shale	2365'
Shale & Lime	2475'
Lime	2625'
Lime & Shale	3265'
Lime	3547'
Lime & Shale	3765'
Lime	4275'
Lime & Shale	4340'
Lime	4353'
TD	4353'

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 31 1970
 CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 8th day of September, 1964.

My Commission Expires:
 January 8, 1968

Shirley Keck
 Shirley Keck, Notary Public

entire