

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.145.30097.0000

LEASE NAME Miller I-

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 31 TWP. 20 RGE. 20 (E) or (W)

COUNTY Pawnee

Date Well Completed 6-16-66

Plugging Commenced 9-10-87

Plugging Completed 9-17-87

LEASE OPERATOR Pickrell Drilling Co, Inc.

ADDRESS Box 1303, Great Bend, Kansas 67530

PHONE# 316-793-5742 OPERATORS LICENSE NO. 5123

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed?                      If not, is well log attached? With application

Producing Formation                      Depth to Top                      Bottom                      T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	251'	None
				4-1/2"	4390'	410.96'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4300' and 4 sacks cement. Shot casing at 2500', 1500', 1000', 600' & 410'. Pulled 13 joints of 4-1/2" casing. Allied squeezed well with 4 sacks hulls and 175 sacks 60/40 pozmix cement with 6% added gel. Maximum pressure was 900 psi and shutin 500 psi.

Name of Plugging Contractor Rockhold Engineering Inc. License No. 5111

Address Box 698 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold  
Box 698, Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 1987

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-87

RECEIVED  
Iona M. Leatherman  
Notary Public  
SEP 23 1987 9-23-1987

My Commission Expires: