

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 31 Twp. 20 Rge. 20 (E) (W) NW NW

Location as "NE/CNW/SW" or footage from lines  
Lease Owner Beardmore Drilling Company  
Lease Name Miller "F" Well No. 1  
Office Address 700 - One Twenty Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 7-20 19 66  
Application for plugging filed 7-20 19 66  
Application for plugging approved 7-20 19 66  
Plugging commenced 7-20 19 66  
Plugging completed 7-20 19 66  
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4391 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface clay		0	20'			
Rock		20'	50'			
Shale		50'	445'	8-5/8"	445'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

0	to 40'	-	10 sacks cement and 1 sack hulls
	40'	-	wood plug
40'	to 260'	-	heavy mud
260'	to 300'	-	12 sacks cement
	300'	-	wood plug
300'	to 465'	-	heavy mud
465'	to 540'	-	25 sacks cement
	540'	-	wood plug
540'	to 4391'	-	heavy mud

RECEIVED  
STATE CORPORATION COMMISSION

AUG 2 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.  
Address 514 Orpheum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Heber Beardmore (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

SUBSCRIBED AND SWORN to before me this 28th day of July, 19 66

My commission expires 7-13-66  
Shirley Ann Jackson Notary Public.



GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

MILLER "F" #1  
 C NW NW SECTION 31-20S-20W  
 PAWNEE COUNTY, KANSAS

COMMENCED: JULY 9, 1966  
 COMPLETED: JULY 21, 1966

OPERATOR - BEARDMORE DRILLING COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	20	SHALE AND SURFACE CLAY	RAN 22 JOINTS OF 8-5/8" CASING, SET @ 445' w/250 SACKS CEMENT.
20	50	POST ROCK	
50	445	SHALE	
445	815	SHALE	DRY AND ABANDONED.
815	1376	SAND	
1376	1406	ANHYDRITE	
1406	2105	SHALE AND SHELLS	
2105	2195	SHALE AND LIME	
2195	2245	LIME	
2245	2620	LIME AND SHALE	
2620	2710	LIME	
2710	3485	LIME AND SHALE	
3485	3605	LIME	
3605	3775	LIME AND SHALE	
3775	4391	LIME	
4391	TD		

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 2 1966  
 INTERMEDIARY DIVISION  
 WICHITA, KANSAS

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NW NW SECTION 31-20S-20W, PAWNEE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*E. E. Hall*  
 \_\_\_\_\_  
 E. E. HALL

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 26TH DAY OF JULY, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

*Barbara J. Layton*  
 \_\_\_\_\_  
 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.