


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pawnee County, Sec. 31 Twp. 20S Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines C NW NE  
Lease Owner Pickrell Drilling Company  
Lease Name Patmon-Seelye "A" Well No. 2  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 31, 1967  
Application for plugging filed August 31, 1967  
Application for plugging approved August 31, 1967  
Plugging commenced August 31, 1967  
Plugging completed August 31, 1967  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4432 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	278'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

FILED  
CORPORATION COMMISSION  
SEP 18 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Heavy mud to 600'. Set plug. Cemented with 100 sacks  
Pozmix. Heavy mud to 240'. Set plug. Cemented with  
Set plug.  
25 sacks cement. Heavy mud to 40'. / Cemented with 10  
sacks cement to bottom of cellar. Plugged rat hole with  
2 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. Sebitts (owner or operator) of the above-described well, being first-duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of September, 19 67

My commission expires May 10, 1970  
L. M. Whiting Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita, Kansas 67202

Rotary Drilling Commenced 8-22-67

Rotary Drilling Completed 8-31-67

LOCATION: Patmon-Seelye "A" No. 2  
C NW NE Section 31-20S-20W  
Pawnee County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: (14 jts.) 8 5/8" surface casing set at 278' and cemented with 155 sacks cement. Circulated. Job complete 6:15 PM, August 22, 1967. No oil string was run. D. & A., plugged August 31, 1967.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

130	Post Rock	<u>C. F. S.</u>
278	Shale & Shells	4360'
278	Cement	4373'
820	Shale, Shells & Red Beds	4379'
1100	Sand	4385'
1378	Shale & Red Bed	4393'
1411	Anhydrite	4432'
2200	Shale	
3513.5	Lime & Shale	
3735	Shale & Sandy Lime	<u>Slope Tests</u>
3740	Heebner	2500'
4235	Lime & Shale	3000'
4375	Shale, Lime & Sand	3500'
4432	Miss., RTD	4000'

S. L. M.  
3891'

RECEIVED  
STATE CORPORATION COMMISSION

SEP 18 1967

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]  
C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 12th day of September, 19 67, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]  
L. M. Whiting  
Notary Public