


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

McPherson County, Sec. 24 Twp. 20 Rge. (E) 4 (W)
Location as "NE/CNW/SW" or footage from lines. SE SE NW
Lease Owner Aladdin Petroleum Corp.
Lease Name Embers Well No. 1
Office Address 809 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 30, 1961
Application for plugging filed January 30, 1961
Application for plugging approved January 30, 1961
Plugging commenced January 30, 1961
Plugging completed January 30, 1961
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3816 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	520'	521'	8 5/8"	521'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'
1 Plug 240' Howco Plug &
1/4 sx hulls
20 sx cement
Heavy mud to 35'
#2 Plug 35' Howco Plug &
1/4 sx hulls 8 sx cement
2 sx cement - Rat Hole

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1961
CONSERVATION DIVISION
Wichita, Kansas
2-10-1961

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
James M. Armour (Employee of Owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour
James M. Armour
817 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of February, 19 61

My commission expires Dec. 29th, 1963
Marjorie Hall
Notary Public.



D R I L L E R ' S L O G

FARM NAME: Embers # 1 LOCATION: SE SE NW Sec. 24-20S-4W
 McPherson County, Kansas
 CONTRACTOR: Shawver-Armour, Inc. ELEVATION: 1488 K. B.
 OWNER: Aladdin Petroleum Corp.
 COMMENCED: January 21, 1961 COMPLETED: January 30, 1961
 CASING RECORD: 521' 8 5/8" w/400 sx cement 2 1/2% CC

FORMATION:TOPS:

Shale & Anhydrite	730	Heebner	2328
Shale & Lime	940	Douglas	2348
Fort Riley	1075	Kansas City	2546
Lime	1160	Mississippian Chat	3216
Shale & Lime	1570	Mississippian Dolomite	3225
Shale & Lime Shells	1910	Kinderhook	3517
Shale & Lime	2261	Viola	3771
Lime & Shale	2345	Simpson Sand	3808
Sand & Shale	2450		
Shale & Lime	2546		
Top Lansing	2575		
Lime	2961		
Lime & Shale	3210		
Shale	3221		
Mississippian	3230		
Lime	3407		
Lime & Chert	3463		
Lime	3517		
Kinderhook Shale	3550		
Shale & Lime	3645		
Shale	3775		
Lime & Shale	3808		
Simpson Sand	3816 1/2		
ROTARY TOTAL DEPTH	3816 1/2		

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 1 1961
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 SEDGWICK COUNTY)

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

BY James M. Armour
 James M. Armour

Subscribed and sworn to before me this
 9th day of February, 1961.

My commission expires Dec. 29th, 1963.

Marjorie Hall
 Marjorie Hall, Notary Public