

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rice County, Sec. 5 Twp. 21 Rge. 6 W (E) (W)

Location as "NE/CNWSW" or footage from lines SE SW NE
Lease Owner Pat Simmons
Lease Name Renolett Well No. b-1
Office Address 5252 North Broadway, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed IO-2 19 55
Application for plugging filed IO-19 19 69
Application for plugging approved IO-20 19 69
Plugging commenced IO-20 19 69
Plugging completed I-5 19 70
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3470' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		1,318'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with sand Sand from 3470' to 3440'. Dumped 5 ar of cement. Mudded hole to 210'. Made 10' of rock bridge. Dumped 35 ar of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 ar of cement, filling to the bottom of the collar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 9 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St Hutchinson Kansas 67501

STATE OF Kansas COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of January, 19 70

My commission expires Dec 29, 1973

Judy Lamb
Notary Public.

15.159.04263.0000

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company, HENRY BENNETT
Farm, Renolett "B" No. 1

SEC. 5 T. 21 R. 6W
SE SW NE

Total Depth, 3470

Comm. 9-22-55

Comp. 10-2-55


County Rice

KANSAS

Shot or Treated.

Contractor, Salina Drilling Corporation, Inc.

Issued, 12-10-55



CASING:
8 5/8 171' w/ 150 sx cmt.
5 1/2 3450' w/ 75 sx cmt.

Elevation, 1648 DF

Production, 45 BO, & 8 BWPD

Figures indicate Bottom of Formations.

clay	30
sand	65
red bed, shells & shale	840
shale & shells	1040
lime & shale	1180
lime & sand	1310
lime & shale	2691
shale	2709
lime	2714
shaley sand	2911
lime w/ shale streaks	3405
shaley conglomerate	3427
cherty conglomerate	3449
chat	3451
chat	3470

Total Depth

TOPS:

Heehner	2691
Totonto	2709
Douglas sand	2714
Lansing	2911
shaley conglomerate	3405
Cherty conglomerate	3427
Mississippi chat	3449

Drilled with Cable Tools to 3455 for show of oil.
Drilled deeper to 3460' recovered more oil.
Completed at 3470' for 45 bbls. oil & 8 bbls. water
per day.

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1969
CONSERVATION DIVISION
Wichita, Kansas