




STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavits
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

_____ Rice _____ County, Sec. 5 Twp. 21 Rge. 6 W. (E) _____ (W)
Location as "NE/CNW/SE/SW" or footage from lines _____ NW/ SE/ SW
Lease Owner _____ Pat Simons
Lease Name _____ Renollett _____ Well No. 4
Office Address _____ 5252 North Broadway, Wichita, Kansas _____ 67219
Character of Well (completed as Oil, Gas or Dry Hole) _____ oil
Date well completed _____ 8-15 1951
Application for plugging filed _____ 10-15 1969
Application for plugging approved _____ 10-16 1969
Plugging commenced _____ 10-14 1969
Plugging completed _____ 10-18 1969
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____ Yes

Name of Conservation Agent who supervised plugging of this well _____ Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3535' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		545'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3535' to 3470'. Dumped 5 sr of cement. Mudded hole to 185'. Made 10' of rock bridge. Dumped 25 sr cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sr of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____ Art Lamb Casing Pulling Co.
Address _____ 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) _____
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of October, 1969

My commission expires January 5, 1970

Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

COPY


15.159.04211.0000

Company- H C BENNETT
Farm- Renollott No. 4

SEC. 5 T. 21 R. 6W
NW SE SW

Total Depth. 3535
Comm. 8-8-51 Comp. 8-15-51
Shot or Treated.
Contractor. Mallard Drlg.
Issued. 10-6-51

County Rice
KANSAS



Elevation. 1670

Production. pump 15 bbls.

CASING:

8 5/8" 125' cem w/125 sxs.
5 1/2" 3402' cem w/50 sxs.

Figures Indicate Bottom of Formations.

surface sand	125
shale, shells	960
shale, lime	1125
lime	1645
lime, shale	1840
shale, shells	2440
lime, shale	2570
lime	3270
lime, shale	3483 RTD
Cable Tools	
slight show of oil	3503-3507
first free oil & gas	3512
overnight fill up 200'	
of oil & 2 bailors wtr.	
soft drilling increase in	
gas	3518
increase of gas	3522
hard formation	3526
soft & more fill up,	
more gas	3531
hard formation & no	
increase	3535
Total depth	
Tops:	
chat	3422

Measurements taken from DF

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1969
CONSERVATION DIVISION
Wichita, Kansas