


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rice County, Sec. 5 Twp. 21 Rge. 6 W (E) (W)  
Location as "NE/CNW&SW&" or footage from lines. SE NE NE  
Lease Owner Cow Gulch Oil Co.  
Lease Name Renollett Well No. 2  
Office Address 909 17th St. Denver, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 7-7 19 52  
Application for plugging filed 11-15 19 72  
Application for plugging approved 11-16 19 72  
Plugging commenced 11-29 19 72  
Plugging completed 12-1 19 72  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3447' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,512'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3447' to 2830'. Dumped 5 sx of cement. Mudded hole to 265'. Made 15' of rock bridge. Dumped 25 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Renov, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 King St. Hutchinson, Kansas 67501  
(Address)

Subscribed and sworn to before me this 1st day of December, 1972

My commission expires January 5, 1974

Judy Lamb  
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


Company- CITIES SERVICE OIL CO.  
Farm- Renollett No. 2

SEC. 5 T. 21 R. 6W  
SE NE NE  
990' S & 330' W of NEc

Total Depth. 3447  
Comm. 6-22-52 Comp. 7-7-52

County Rice KANSAS

Shot or Treated.  
Contractor. Lohmann-Johnson Drilling Co., Inc.  
Issued. 1-24-53



CASING:  
8 5/8 262' w/ 150 sx cement ✓  
5 1/2 3421' w/ 150 sx cement ✓

Elevation 1634

Production. 94 BO, 28 BW 24 hrs

Figures indicate Bottom of Formations.

sand	35
red bed	263
red bed & shale	577
shale & shells	900
shale & sand	1075
shale & broken lime	1102
shale & shells	1235
shale & broken lime	1390
broken lime	1535
broken lime & shale	1680
lime & shale	2280
broken lime	2390
shale & lime	2560
broken lime	2665
lime & shale	2889
lime	2937
lime & shale	3075
lime	3097
lime & shale	3200
lime	3243
lime & shale	3330
lime	3384
lime & shale	3425
RTD 3425 - SLM 3425	
chert	3447
Total Depth	

TOPS.	
Lansing	2896
Conglomerate	3385
Mississippi	3418
Penetration	29

Sand-fractured w/ 2000# sand & 220  
BO in 30 min. treating pressure  
3000-1500#

45' oil in 1 hr. at 3447

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 16 1972  
CONSERVATION DIVISION  
Wichita, Kansas