


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County, Sec. 5 Twp. 21 Rge. 6 W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Pat Simmons  
Lease Name Ronollett Well No. I  
Office Address 5252 North Broadway, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 2-20 19 50  
Application for plugging filed 4-7 19 70  
Application for plugging approved 4-8 19 70  
Plugging commenced 4-9 19 70  
Plugging completed 4-10 19 70  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3501' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2537'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3501' to 3450'. Dumped 5 ex of cement. Mudded hole to 215'. Made 10' of rock bridge. Dumped 6 Yrds Ready-Mix Cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 King St. Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13 th day of April, 19 70

My commission expires Jan 5, 1974  
Judy Lamb  
Notary Public.

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 E. Murdock,

Wichita, Kansas

COPY

15.159.04399.0000

Company - H. C. BENNETT

Farm - Renollet

No. 1

SEC. 5  
SW SW SW

T. 21

R. 6W

Total Depth. 3501

Comm. 12-28-49

Comp. 2-20-50


Shot or Treated.

Contractor.

Issued. 5-6-50

County. Rice

KANSAS



Elevation. \_\_\_\_\_

Production. 62 EO

CASING:

8" 145'

5" 3479' cem. w/75 sx.

DEPTHS FROM R. B. 3' above rig floor & 4' above ground. Figures indicate Bottom of Formations.

Sample Log.

lime gry dense xyln	3316
shale gry	3319
lime gry xyln	3335
lime gry dense xyln & thin shale	
partings	3352
shale maroon	3355
lime gry dense	3364
shale drk	3367
lime gry dense xyln	3393
(spotted porosity & spotted oil sat.	
3382-3385	
shale lgt grn	3396
shale gry & thin lime	
stringers	3408
shale maroon	3410
lime gry dense	3414
shale drk	3434
lime lgt dense	3437
shale drk	3449
shale var. colo. cong.	3468
chert var. colo. cong.	3477
chert & tripoli	3485
neg. acid action	
chert & tripoli ?	3501
good porosity, good oil sat. & odor	
3479-3485	
Total Depth	3501

Tops: Rig floor depths

V.C. shale congl	3446
cherty congl.	3465
Miss.	3474

RECEIVED  
STATE CORPORATION COMMISSION  
APR 8 1970  
CONSERVATION DIVISION  
Wichita, Kansas