


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 N. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines Rice County, Sec. 5 Twp. 21 Rge. 6W (E) (W) NE NW SE

Lease Owner Pat Simmons

Lease Name Engelland Well No. 6

Office Address 5252 North Broadway, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 8-16 1956

Application for plugging filed 12-29 1969

Application for plugging approved 12-30 1969

Plugging commenced 12-31 1969

Plugging completed 1-6 1970

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3476' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		1,364'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3476' to 3440'. Dumped 5 ex of cement. Mudded hole to 220'. Made 10' of rock bridge. Dumped 25 ex of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 ex of cement, filling to the bottom of the hole.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 9 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King St Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.

Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 King St. Hutchinson, Kansas 67501

(Address)

SUBSCRIBED AND SWORN to before me this 6th day of 6th January, 19 70

My commission expires Dec 29, 1973

Judy Lamb  
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


COPY

Company: H. C. BENNETT  
Farm: Engalland No. 6

SEC. 5 T. 21 R. 6W  
NE NW SE

Total Depth: 3476  
Compl. 8-3-56 Comp. 8-16-56  
Shot or Treated.  
Contractor: Saline Drig Corp., Inc.  
Issued: 11-10-56

County Rice  
KANSAS



Elevation: 1656 D.F.

Production: 20 BO + 5 BW

CASING:

8 5/8" 224.43' cem w/175 sx.  
5 1/2" 3455.4' cem w/ 75' sx.

Figures indicate Bottom of Formations.

sand	50
red bed, shale, shells	720
shale, shells	1100
shale, shells, sdy	
lime	1360
lime sdy, lime	1500
shale, lime	1640
lime	1690
lime, shale	1765
shale, shells	2170
lime, shale	2290
shale, shells	2400
shale, lime	2490
lime	2655
lime, sand	2735
sand	2830
lime	2925
lime, sand	2990
lime	3425
congl., lime	3453
lime	3455

Total Depth Rotary  
Drilled w. Cable Tools  
to 3466  
Slight show of oil  
Deepened to 3476  
Total Depth

Tops:  
Shaley Conglomerate 3420  
Cherty Congl. 3441  
Mississippi 3449

Fractured.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 3 1 1969  
CONSERVATION DIVISION  
Wichita, Kansas