


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County, Sec. 5 Twp. 21 Rge. 6 W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Pat Simons
Lease Name Engelland Well No. 5
Office Address 5252 North Broadway, Wichita, Kansas 67219
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 10-19 1955
Application for plugging filed 5-26 1970
Application for plugging approved 5-27 1970
Plugging commenced 5-27 1970
Plugging completed 5-28 1970
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? VGS

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3470' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2		2.532'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3470' to 3440'. Dumped 5 sack cement. Mudded hole to 200'. Made 10' of rock bridge. Dumped 25 sack of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sack of cement, filling to the bottom of the collar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of May 1970

[Signature]
Notary Public.

My commission expires January 5, 1974

ROTARY DRILLER'S LOG

Engelland #5

Elevation: 1655 D. F.

Legal Description: NE NE SW Sec. 5, Twp. 21, Range 6 W, Rice County, Kansas.

Casing Record: 175' 8 5/8" with 240 Foz. 2400. 3453' 5 1/2" cemented with 75 sacks Foz.

Operator: ~~CANNON~~ Cannett
H.C.
Wichita, Kansas.

Contractors: Salina Drilling Corporation, Inc.
Box #566,
Salina, Kansas.

Well Commenced: 10-3-55

Geologists: Charles C. Brown,
252 Hale Bldg. Wichita, Mo.

Well Completed: 10-19-55

Surface Clay	30
Sand	70
Shale, Shells, & Red Bed	130
Shells and Red Bed	177
Red Red-Shale-Shells	310
Shale and Shells	1290
Lime and Shale	1490
Lime	1610
Lime and Shale	2505
Lime	2695
Lime, Shale, and Sand	2900
Lime	3215
Lime and Shale	3260
Lime	3365
Lime & Shale	3437
Cong. & Miss.	3455 TD

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1970
CONSERVATION DIVISION
Wichita, Kansas

Drilled down with Cable
Tools to 3456', no show.
Drilled to 3465' in Chert
for show of oil, drilled to
TD 3470'
Completed for 20 bbls. oil
15 bbls. water

Cherty Conglomerate-----3437' TOPS PICKED BY GEOLOGIST Mississippi-----3451'

The above Rotary Driller's Log is complete and correct to the best of my knowledge.

Tom J. Hallam

Subscribed and sworn to before me this 20th day of October, 1955.

My commission expires 2-26-58

Tom M. Culbough
Notary Public