

MAR 13 2001

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

CONSERVATION DIVISION  
 WICHITA, KS

LEASE OPERATOR F.G. Holl Company, L.L.C.  
 ADDRESS PO Box 780167, Wichita, KS 67278  
 PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

LEASE NAME Renollet B  
 WELL NUMBER 205  
4290 - Ft. from S Section Line  
4290 Ft. from E Section Line  
 SEC. 5 TWP. 21S RGE. 6W (E) or (W)  
 COUNTY Rice

Character of Well oil  
 (Oil, Gas, D&A, SWD, nput, Water Supply Well)  
 The plugging proposal was approved on 2/20/01 (date)

Date Well Completed  
 Plugging Commenced 2/23/01  
 Plugging Completed 2/27/01

by Jack Luthie (KCC District Agent's Name).

ACO-1 filed? unknown If not, is well log attached? not available to us

Producing Formation Miss Depth to Top 3468 Bottom 3478 T.D. 3535

Show depth and thickness of all water, oil and gas formations.

OIL GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	210	none
				5 1/2	3534	2237

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each section.

Sanded to 3400, baled 5 sacks cement. Shot pipe at 2416, 2237, pulled 28 jts. Up to 1100' and pumped 35 sacks cement at 1100. Pulled 11 jts. to 650, pumped 35 sacks cement. Pulled 10 jts. to 260', circulated with 133 sacks.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 415 East Main, Sterling KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C.

STATE OF KANSAS COUNTY OF SEDGWICK, ss

ELWYN H. NAGEL (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed thereon, and the same are true and correct, so help me God.


(Signature) Elwyn H. Nagel

(Address) PO Box 780167, Wichita, KS 67278

SUBSCRIBED AND SWORN TO before me this 14th day of March, 2001 19

Sharon J. Clark  
 Notary Public

My Commission Expires: 3-16-03



USE ONLY ONE SIDE OF EACH FORM

OR