

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County, Sec. 4 Twp. 21 Rge. 6 (E) (W)
S/2 SW SE

Location as "NE/CNWSWK" or footage from lines.
Lease Owner Sterling Drilling Company
Lease Name Johnson A#9 Well No. _____
Office Address Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/22/72 _____ 19____
Plugging completed 1/25/72 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3453 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	173	none
				5 1/2"	3434'	2965'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3453', ran sand to 3400' and dumped 5 sacks of cement. Loaded hole, shot pipe at 2967', pulled 93 joints. Set rock bridge 210 to 200' and dumped 35 sacks of cement. Mud to 40', set rock bridge and dumped 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of January, 19 72

My commission expires _____
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Notary Public.

T-46.

15.159.20369.0000

RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1972
CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

END

WELL LOG ----- JOHNSON "A" #9
Located: Approximately S/2 SW NE, Section 4-21S-6W,
Rice County, Kansas

OWNER: Forchild Interests and Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 21, 1971
COMPLETED: May 27, 1971

TOTAL DEPTH: 3436'

LOG

CASING RECORD

0 - 35	Sand
35 - 176	Red Bed and Shale
176 - 300	Red Bed
300 - 1150	Shale and Shells
1150 - 2475	Lime and Shale
2475 - 2755	Lime and Shale - Sand
2755 - 2892	Lime and Shale
2892 - 2928	Lime
2928 - 2990	Sand
2990 - 3436	Lime

Ran 4 joints 8 5/8" casing - 161'
cemented at 173' K.B. with 160 sacks
60/40 3% HA5. Plug down at 5:45 PM,
5-21-71.

Ran 108 joints 3 1/2" threads off
5 1/2" 14# 8rd tested 4000#, set
at 3434' with 75 cu. ft. salt saturated
cement. Plug down @ 11:10 PM, 5-26-71.