


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plot

Rice County, Sec. 4 Twp. 21 Rge. 6 (E) (W)
Location as "NE/CNWSW" or footage from lines NW NW NE
Lease Owner Sterling Drilling Company
Lease Name Johnson A#7 Well No.
Office Address Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/26/72 _____ 19____
Plugging completed 1/31/72 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3439' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	137	none
				5 1/2"	3430	2585'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3437', ran sand to 3400' and dumped 5 sacks of cement.
Loaded hole, shot pipe at 2947', 2887', 2796', 2697', 2609', 2543',
pulled 82 joints. Bailed hole to 210', set 10' rock bridge and ran 35
sacks of cement. Mud to 40', set 10' rock bridge and ran 10 sacks cement.

PLUGGING COMPLETE.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and Sworn to before me on this 31st day of January, 1972.
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires Feb. 15, 1975

31st day of January, 1972
Margaret Melcher
Notary Public.

T-44

STERLING DRILLING CO.

STERLING, KANSAS

RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1972
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG ----- JOHNSON #7

Location - NW/4 NW/4, NE/4 Section 4-21-6, Rice County, Kansas

Owner - Sterling Drilling Company
Rotary Drilling Contractor - Sterling Drilling Company
Cable Tools Contractor - Ice Oil Field Service, Inc.

Commenced - 1-13-52
Completed - 1-24-52 (w/r)
2 2- 4-52 (w/c.t.)

Total Depth - 3431' (w/r)
- 3433½' (w/c.t.)

ELEVATION: 1620 IF
1617 Gr

LOG

0- 60 Surface Clay and Sand
60- 140 Shale and Shells
140- 650 Shale, Shells, Red Bed & Salt
650- 850 Shale and Salt
850- 975 Shale and Lime Shells
975-2320 Lime and Shale
2320-2640 Lime
2640-2675 Shale and Lime
2675-2760 Shale
2760-3280 Lime
3280-3389 Lime and Shale
3389-3411 Conglomerate
3411-3431 Chat

CASING RECORD

138' of 8-5/8" Surface Pipe
Cemented at 137' with 100 Sacks Victor
Cement
3456' of 5½" O. D. Casing
Set at 3430 with 75 Sacks Atlas Sack Cement

CABLE TOOLS RECORD: Cleaned out to rotary total depth, 3431'. Made 1' new hole.
Filled up 1000' in 45 minutes. Drilled to 3433½'. Filled up to 2568' of oil.
Swab testing 6.68 bbls. per hr. for 1½ hrs. Running tubing to hydrafrac.
Sand pump and clean up after hydrafrac. Swabbing well down showed increase.
Put on pump.