


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rice County. Sec. 4 Twp. 21S Rge. (E) 6 (W)  
Location as "NE/CNW/SW" or footage from lines NW NE NE  
Lease Owner Sterling Drilling Company  
Lease Name Johnson "A" Well No. 4  
Office Address Sterling, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed November 6, 19 68  
Application for plugging approved November 7, 19 68  
Plugging commenced November 18 19 68  
Plugging completed November 22 19 68  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Uneconomical to produce  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tolman  
Producing formation Mississippi Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3445 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi				5-1/2	3387	None 2928

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

5 1/2' @ 3387 w/50 sacks.  
Sanded hole 3445' to 3375'.  
5 sacks cement @ 3375'.  
Shot pipe @ 3031' and 2904'.  
Pulled 2927.99' (92 jts.) 5 1/2' casing.  
Mudded hole to 210'.  
Rock bridge 210'-200'.  
30 sacks cement @ 200'.  
Rock bridge 40'-30'.  
10 sacks cement to surface.  
Plugging complete.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 16 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Braden-Deem, Inc.  
Address 210 One Twenty Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
210 One Twenty Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of December, 1968

My commission expires March 21, 1970

[Signature]  
Notary Public.

WELL LOG - - - - - JOHNSON NO. 4

Location - NW 1/4 N. of Section 4-215-77

Commenced - 9-13-48  
Completed - 9-25-48 (w/r)  
10-13-48 (c/t)

Owner - J.A. Davis & J.H. Child, et al  
Contractor - Sterling Drilling Company

Total Depth 3587 (w/r)  
3445 (c/t)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 7 1968  
CONSERVATION DIVISION  
Wichita, Kansas

ELEVATIONS

1601 D.P.  
1579 Gr.

LOG

0- 103	Surface sand- Clay shale
103- 700	Shale
700- 800	Salt and Shale
800-1350	Shale and Linc
1350-1465	Linc and Shale
1465-1775	Shale and Linc
1775-1965	Shale
1965-2350	Shale and Linc
2350-2630	Linc
2630-2750	Shale
2750-2900	Linc
2900-2960	Sand
2960-3200	Linc
3200-3375	Shale
3375-3384	Conglomerate
3384-3387	Chat
3387-3445	Cable Tool

GASLITE RECORD

Ran 102' 2-5/8" casing  
Completed with 100 Jacks current

Ran 107 Jts. 5" casing  
(set at 3384)

PRODUCTION

Producer