


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 4 Twp. 21S Rge. (E) 6 (W)

Location as "NE/CNW/SW" or footage from lines SE NW NE
Lease Owner Sterling Drilling Co.
Lease Name Johnson "A" Well No. 3
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed November 6, 1968
Application for plugging approved November 7, 1968
Plugging commenced November 11 1968
Plugging completed November 16 1968
Reason for abandonment of well or producing formation
Uneconomic to produce
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Gilbert Tolman
Producing formation Mississippi Depth to top Bottom Total Depth of Well 3450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi				8-5/8"	114	None
				5-1/2"	3424	2910

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5-1/2" @ 3424' w/50 sacks.
Sanded hole 3450-3400'. 5 Sacks cement @ 3400'.
Shot pipe @ 3010 and 2887'.
Pulled 2909.98' (92 jts) 5 1/2" casing.
Mulled hole to 210'.
Rock bridge 210'-200'.
30 sacks cement @ 200'.
Rock bridge 40'-30'.
10 sacks cement to surface.
Plugging complete

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Braden-Deem, Inc.
Address 210 One Twenty Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*
210 One Twenty Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of December, 1968

My commission expires March 21, 1970
[Signature] Notary Public.

WELL LOG ----- JOHNSON NO. 3

Location - SE NW NE of Section 4-218-GW, Rice County, Kansas.

Commenced - 8-28-48

Completed - 9-7-48 (w/r)
9-20-48 (c/t)Owner - J. A. Davis and J. H. Child, et al
Contractor - Sterling Drilling CompanyTotal Depth - 3427 (w/r)
3450 (c/t)RECEIVED
STATE CORPORATION COMMISSIONNOV 7 1968
CONSERVATION DIVISION
Wichita, KansasLOG

0- 106	Surface Clay, Sand & Shale
106-205	Shale
205- 850	Shale and Salt
850-1115	Shale and Shells
1115-1300	Shale and Lime
1300-1450	Lime
1450-2240	Shale and Lime
2240-2320	Shale
2320-2575	Lime
2575-2650	Bro. Lime
2650-2760	Shale
2760-2925	Lime
2925-2985	Sandy Lime
2985-3255	Lime
3255-3325	Lime and Shale
3325-3406	Shale
3406-3423	Conglomerate
3423-3427	Chat
3427-3450	Cable Tools

CASING RECORD114' 8-5/8" Surface Pipe
Cemented with 125 Sacks Cement.3437' 5 1/2-inch O.D. Casing
(Set 3' off bottom)
Cemented with 50 Sacks Cement.PRODUCTION

Producer.