


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 4 Twp. 21 Rge. 6 (E) (W)
Location as "NE/CNW/SW" or footage from lines. NW SE NE
Lease Owner Sterling Drilling Company
Lease Name Johnson A#2 Well No.
Office Address Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/28/71 19
Plugging completed 10/2/71 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3439 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	105	none
				5 1/2"	3401	1612'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3439', ran sand to 3390' and dumped 5 sacks of cement. Loaded hole, shot pipe at 3012', spotted 35 barrels of oil, worked tension at no gain. Pumped 70 barrels water, shot pipe at 2492', 2006', 1802', 1612', worked pipe loose and pulled 50 joints. Bailed fluid to 190', set 10' rock bridge and dumped 35 sacks of cement. Mudded to 40', set 10' rock bridge and dumped 10 sacks of cement.

plugging complete.

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
CHASE, KANSAS
(Address)

Subscribed and Sworn to before me this 4th day of October, 1971
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires Feb. 15, 1975

Margaret Melcher
Notary Public.

T-39.

Location - NE 1/4 NE of Section 4-21S-6W, Rice County, Kansas.

Owner - J. A. Davis and J. H. Child, et al
Contractor - Sterling Drilling Company

Commenced - 7-25-48
Completed - 8-4-48 (w/r)
8-27-48 (c/t)

Total Depth - 3416 $\frac{1}{2}$ (w/r)
3439 (c/t)

ELEVATION: 1604 D.F.
1602 Gr.

LOG

0- 20	Surface Sand
20- 105	Clay and Red Shale
105- 400	Shale
400-1000	Shale, Shells & Salt
1000-1200	Shale & Lime
1200-1660	Lime
1660-2080	Shale & Lime
2080-2260	Shale
2260-2390	Lime & Shale
2390-2625	Lime
2625-2750	Shale
2750-3215	Lime
3215-3401	Shale
3401-3416 $\frac{1}{2}$	Chatt
3416 $\frac{1}{2}$ -3439	Cable Tools

CASING RECORD

105' 8-5/8" Surface Pipe
Cemented with 50 Sacks Cement

3413' 5 $\frac{1}{2}$ -inch O.D. Casing
(Set at 3409)
Cemented with 50 Sacks Cement

PRODUCTION

Producer.

Filled up. 2700' in 16 hours.

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1971
CONSERVATION DIVISION
Wichita, Kansas