


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rice County. Sec. 4 Twp. 21 Rge. 6 (E) W (W)
SW SW NW



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines
Lease Owner Sterling Drilling Company
Lease Name Cleavinger Well No. 1
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11-16-65 _____ 19____
Plugging completed 11-18-65 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3471 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	131'	None
				5-1/2"	3429'	3099'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, pushed 5 1/2" plug to 3425' on top of 4" liner, sanded with 10 gallons of sand and dumped 5 sacks of cement on sand with dump bailer. Pulled 5 1/2" casing, bailed hole to 160', set rock bridge to 150' and dumped 25 sacks of cement @ 150'. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1965

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of November, 19 65

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

Location - West Half ($W\frac{1}{2}$) of the Northwest Quarter ($NW\frac{1}{4}$) of Section 4-21-6,
Rice County, Kansas.

Owner - Harold Seeger, et al
Contractor - Sterling Drilling Company

Commenced - September 27, 1947
Completed - October 9, 1947 (with rotary)

Total Depth - 3430' (with rotary)
3458' (cable tools)

Casing Record

131' 8-5/8" Surface Pipe
Cemented with 100 Sacks Cement

3430' 5 $\frac{1}{2}$ -inch Pipe

LOG

0- 40	Sand
40- 131	Shale & Lime
131- 325	Shale & Red Bed
325- 975	Shale & Lime
975-1260	Shale & Lime
1260-1810	Lime
1810-1950	Shale & Lime
1950-2285	Shale
2285-2450	Shale & Lime
2450-2710	Lime
2710-2795	Shale
2795-3315	Lime
3315-3385	Lime & Shale
3385-3420	Shale
3420-3430	Conglomerate
3430-3458	Cable Tools
3458	Total Depth

Production

Producer. Estimated 35 Bbls.
Got Gas & Oil from 3453-3458.

RECEIVED
STATE OF KANSAS
OCT 18 1947
CONSERVATION DIVISION
WICHITA, KANSAS