

15.159.21515.0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Rice SEC. 4 TWP. 21S RGE. 6W X/W  
 Location as in quarters or footage from lines:  
C N/2 NW NW


Lease Owner Sher-Lon Corporation  
 Lease Name Cleavenger #1 Well No. 1  
 Office Address 320 South Broadway, Sterling, Kansas 67579  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed November 11, 1982  
 Application for plugging filed November 11, 1982  
 Plugging commenced 11:00 PM, November 11, 1982  
 Plugging completed 12:00 PM, Midnight, November 11, 1982  
 Reason for abandonment of well or producing formation Dry Hole

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merlan W. Unruh

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3300"

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
					215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
 50 sasks 50/50 Pozmix with 3% cc at 300';  
 10 sasks cement, solid bridge at 40' with  
 1/2 sack hulls and Howco plug.  
 10 sasks cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
 F. A. Wuellner, Secretary

(Address)  
 P. O. Box 129, Sterling, Ks. 67579

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1982.

[Signature]  
 Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85



RECEIVED  
 STATE CORPORATION COMMISSION

DEC 2 1982

CONSERVATION DIVISION  
 Wichita, Kansas

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- CLEAVENGER #1

Located: C N/2 NW NW, Section 4-21S-6W, Rice County,  
Kansas

OWNER: Sher-Lon Corporation

ROATYR DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 7, 1982

COMPLETED: November 11, 1982 (Midnight)

TOTAL DEPTH: 3300'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 50 Sand	Ran 5 joints 8 5/8" casing. 202.69' pipe set at 215' K.B. Cemented with 150 sacks 50/50 Pozmix and 50 sacks Common with 3% cc. Plug down at 2:45 PM, 11-7-82, by Howco.
50 - 930 Shale	
930 - 3300 Lime and Shale	Plugged.

Deviation Surveys: 1° at 1613'  
3/4° at 2506'

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1982  
CONSERVATION DIVISION  
Topeka Kansas