

To: 1 051148  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5171  
Operator: TXO Production Corporation  
Name & Address: 1660 Lincoln Street, Suite 1800  
Denver, CO 80264

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address Box 187, Medicine Lodge, KS

Company to plug at: Hour: 9:30 a.m. Day: 4 Month: 4 Year: 19 89

Plugging proposal received from Elmo Morgenstern  
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4795' PBTD 4780' Perfs at 4672-84'  
1st plug sand back to 4620' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

APR 7 1989

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent  Part  None

Operations Completed: Hour: 10:45 a.m. Day: 4 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4620' and dumped 4 sx cement on top of sand through bailer,  
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Maximum pressure 600 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by B.J. Titan. Recovered 2500' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

IN WITNESS WHEREOF, I observe this plugging.

DATE 4-19-89

Signed Richard M. Tracy  
(TECHNICIAN)

INV. NO. 24356

4-4-89 318 R  
API NUMBER 15- 097-21,018 -0000  
SW NW SE, SEC. 12, T 28 S, R 16 WXR  
1650 feet from S section line  
2310 feet from E section line  
Lease Name Ross "C" Well # 2  
County Kiowa 15600  
Well Total Depth 4800 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 405