

To: 1 090713  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 097-21,410 - 0000  
App. N/2 SW NW, SEC. 21, T. 28 S, R. 17 W/E

7-25

1600 feet from NE section line  
600 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6926

Lease Name Peck Well # 1

Operator: Advantage Resources, Inc.

County Kiowa 160.87

Name: 1775 Sherman St., Ste. 1375

Well Total Depth 4950 feet

Address Denver, CO 80203-4316

Conductor Pipe: Size            feet

Surface Casing: Size 8 5/8 feet 446

Abandoned Oil Well            Gas Well            Input Well            SWD Well            O&A X

Other well as hereinafter indicated           

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 10:30 a.m. Day: 25 Month: 7 Year: 19 96

Plugging proposal received from Harvey Moore

(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite Base 1160'

1st plug at 1160' with 50 sx cement, 2nd plug at 480' with 50 sx cement, **RECEIVED**

KANSAS CORPORATION COMMISSION

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement, **JUL 29 1996**

5th plug to circulate mousehole with 10 sx cement.

CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 12:30 p.m. Day: 25 Month: 7 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 1160' with 50 sx cement,

2nd plug at 480' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugged water well with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

11/22/96 (if not) observe this plugging.

Signed [Signature]  
(TECHNICIAN)

**INVOICED**  
DATE 8-6-96  
INV. NO. 46167

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 7-14-96

State of Kansas 097-21,410

FORM MUST BE TYPED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

SGA7... Yes... No

Must be approved by the K.C.C. five (5) days prior to commencing well.

ALL BLANKS MUST BE FILLED

Expected Spud Date July 15, 1996

Spot App. C-N/2 SW - NW Sec 21 Twp 28S S, Rg 17W East West

OPERATOR: License # 6926
Name: ADVANTAGE RESOURCES, INC.
Address: 1775 Sherman Street - Suite 1375
City/State/Zip: Denver, Colorado 80203-4316
Contact Person: Lou Bortz
Phone: 303/831-1912

1600 feet from South (North) line of Section
600 feet from East (West) line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Kiowa
Lease Name: PECK Well #: 1
Field Name:
Is this a Prorated/Spaced Field? yes X no

CONTRACTOR: License #: 5929
Name: DUKE DRILLING CO., INC.

Target Formation(s):
Nearest Lease or unit boundary: 600'
Ground Surface Elevation: EST. 2205 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec X Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWD ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 180' 180'
Depth to bottom of usable water: 180' 230'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 430'
Length of Conductor pipe required: N/A
Projected Total Depth: 4950'

If OWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Formation at Total Depth:
Water Source for Drilling Operations:
X well ... farm pond ... other
(APPLY FOR FROM DWR)

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Will Cores Be Taken? yes X no
If yes, proposed zone:

Exp. 1/9/97

AFFIDAVIT

240' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 20-1-101 et. seq. It is agreed that the following minimum requirements will be met:

RECEIVED

JUL 29 1996

Well Plugged

Pusher: Howard Moore
SPUD DATE: 7-17-96 INIT. (date)
LENGTH SURFACE PLANNED: 450'
RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2" @ 446 CONDUCTOR
ANHYDRITE T- B- 1160 ELEVATION
TD 4950 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1160 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 480 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL 10 SX (Irr. Well Pond Hauling)
TECHNICIAN Sam DATE 7-23-96
TYPE OF CEMENT 60/40 67
STARTING TIME 10:30 (AM/PM) DATE 7-24-96
COMPLETION TIME 12:30 (AM/PM) DATE 7-25-96
CEMENT COMPANY Allied Cement

CONSERVATION DIVISION WICHITA, KS