

2 100512

7-20 15.113.04538.0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1937

SW SE SW, SEC. 20, T 21 S, R 1 W/E

330 feet from N/S section line

3630 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5663

Lease Name Kinblade Well # 4 (Inj.)

Operator: Hess Oil Company

County McPherson 107.90

Name & Address P. O. Box 1009

Well Total Depth 3320' feet

McPherson, KS 67460

Conductor Pipe: Size 7" feet 3283'/300 SX

316-241-4640

Surface Casing: Size 10" feet 148/150 SX

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated O.H. 3283'-3320'

Plugging Contractor Hess Oil Company License Number 5663

Address Box 1009 McPherson, KS 67460

Company to plug at: Hour: 10:00 Day: 20 Month: 7 Year: 19 89

Plugging proposal received from Bryan Hess

(company name) Hess Oil Company (phone) \_\_\_\_\_

were: Sand bottom 50' above open hole - dump 10 sx cement - shoot & pull pipe - redimix from 250' to surface

Plugging Proposal Received by Sanders  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:05p Day: 20 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT Could not get past 1200' - ran plug to 1195' - dumped

5 sx cement - did not pull 7" - ran 1-1/2" down to 180+ on outside and circ

4 yds slurry mix - pushed plug to 250' on inside and dumped 2-3/4 yds rock

mix to surface.

Remarks: Plenert #496 & #498

**INVOICED** (If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 7-31-89

Signed J. L. Sanders  
(TECHNICIAN)

INV. NO. 25460