

To: 1 090008  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-1  
API NUMBER 13- 093-20,660.0000  
C, E/2, SEC. 16, T 21, S, R 38 W/EX  
2640 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5249

Lease Name Hildebrand Well # 1

Operator: Osborn Heirs Company

County Kearny 99.12

Name & Address P.O. Box 17968

Well Total Depth 3050 feet

San Antonio, TX 78286

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 333

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 11 a.m. Day: 1 Month: 10 Year: 19 90

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling Service (phone) 316-675-8349

work: 5 1/2" at 3048' w/700 sx cement, PBD 2760', Perfs at 2842-2916', CIBP @ 2760, 2586-2710'

Pump down 5 1/2" with 3 sx hulls, 25 sx cement, 5 sx gel, 20 sx cement, 3 sx gel, and 40 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 12:45 p.m. Day: 1 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT Pumped down 5 1/2" with 2 1/2 sx hulls, 25 sx cement, 5 sx gel, 20 sx cement, 3 sx gel, and 44 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 4 1990

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-19-90

INV. NO. 29671

Signed [Signature] (TECHNICIAN)