

KCC OIL/GAS REGULATORY OFFICE

DATE: 01/05/01


[X] New Situation
 [] Response to Request
 [] Follow-Up

OPERATOR: Sunflower Well ServiceLICENSE #: 30280LOCATION: SE-SW-NE, SEC: 24, T: 21S, R: 2WADDRESS: P.O. Box 341LEASE: Duerksen NO.: 1ADDRESS: Canton, KS 67428COUNTY: McPhersonPHONE #: 316-628-4723LEASE INSPECTION:COMPLAINT:FIELD REPORT: XREASON FOR INVESTIGATION: Clarify if the Duerksen #1 or Duerksen #2 was plugged.PROBLEM: Confusing on well number and location concerning plugging of 09/25/92.PERSONS CONTACTED: None.FINDINGS: The Duerksen #1 well located in the SE-SW-NE of the section was plugged on 09/25/92. There is no well at this location. The plugging contractor supplied incorrect information on the CP-1 calling the plugged the Duerksen #2. The spot location given on the CP-1, filed with the K.C.C., was the SE-NW-NE of the section. The Duerksen #2 well is an oil well, on the location, with rods and tubing in place at the time of the inspection. The Duerksen #2 well is to be converted to an U.I.C. well in the near future.PHOTOS TAKEN: None.ACTION/RECOMMENDATIONS: Correct CP-2/3 on file with central office and District #2 office.

Michael R. Wilson
P.I.R.T. II
01/16/01

CC: Mike Engelbrecht

B. E. SHELTON #1 DUERKSEN 24-21-2W
 WICHITA, KS. SE SW NE
 Contr. ASPEN DRILG. COMPANY Cty. MC PHERSON
 Geol. WALTER MARTZ Pool WINSINGER
 E. 1497 KB Cm. 7/6/69 Cp. 10/9/69 IPPMP 79 BOPD + 48%
 WTR/HUNT 3368-72
 API 15-113-20,073



LOGTops	Depth	Datum	Csg.
			8-5/8" 268/160 SX
			4 1/2" 3438/100 SX
MISS	2976	-1479	DST 3364-3375/1', 1740' GIP, 60'
KIND	3296	-1799	CL OIL, 60' MDY GSY OIL, 30'
HUNT	3364	-1867	O&GCM, 30' SO&GCMW, BHP
MAQ	3380	-1883	707#/30"-707#/45", FP 31-94#
LTD	3439	-1942	
			CO TO 3407, PF 16/3368-72, SWB
			DN, NO FU, 250 MA, SWB LD & SWB
			5 BFPH, 10% w/1', 1000 REG ACID
			SWB LD, FU 600' OIL, 960' M&W/
			12 HRS, SWB 10 BFPH/4 HRS, 50%W
			POP, PMP 48 BOPD + 22% WTR,
			NO CORES

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

15.113.20073.0000

9-25

2-010014 III R

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 8 1992

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-113-20,075.0000 ²⁰⁰⁷³

~~SE NW NE~~, SECTION 24 TOWNSHIP 21 RANGE 2W

OPERATOR LICENSE # 30280 4290 FEET FROM S SECTION LINE
1650 FEET FROM E SECTION LINE

OPERATOR Sunflower Well Service
NAME & P. O. Box 341
ADDRESS Canton, KS 67428

LEASE NAME: Duerksen #2 1

COUNTY: McPherson

WELL TOTAL DEPTH: 3429' 111.44

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 210'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Sunflower Well Service
ADDRESS: P. O. Box 341, Canton, KS 67428 LICENSE: 30280

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 25 MONTH: 9 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Bud Davis
COMPANY NAME: Sunflower Well Service PHONE: 316-628-4723

WERE: Sand to 3310' & top w/4 sx cmt - perms 3360' - 3370' -
shoot pipe off & circ cmt from 350 to surface.

PLUGGING PROPOSAL RECEIVED BY: Dave Wertz

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 12:00 DAY: 25 MONTH: 9 YEAR: 1992

ACTUAL PLUGGING REPORT:
Shot pipe off @ 888' - built bridge at 330' & filled
csg w/slurry mix - used 99 sx cmt & 396 gallons water -
retrieved 888' of 4-1/2" csg
Sanded to 3310' & topped w/4 sx.

REMARKS: Plenert Concrete #4204

I DID OBSERVE THIS PLUGGING.
INVOICED

DATE 10-29-92

INV. NO. 36622

Michael R. Wilson (AGENT)