

To: 1 110027
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 055-20,657.0000

C NE NW, SEC. 18, T 21 S, R 33 W/EX
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Lease Name Crist Well # 1-18

Operator: Mustang Drilling & Exploration, Inc.
Name & Address P. O. Box 1609
Great Bend, KS 67530

County Finney
Well Total Depth 4835 Mississippi 57.14 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Mustang Drilling, Inc. License Number 4813

Address P. O. Box 1609, Great Bend, KS 67530

Company to plug at: Hour: 11:00 am Day: 10 Month: March Year: 19 86

Plugging proposal received from Bill Nelson

(company name) Mustang (phone) 316-792-7323

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2913 GL
Anhydrite 2086'

1st plug 50' above and 50' below the Council Grove Chase Unit with 100 sx cement

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:00 pm Day: 10 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 3300' with 100 sx cement, 2nd plug at 2100' with 40
sx cement, 3rd plug at 470' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOLCED
I (Party) do (not) observe this plugging.

DATE MAR 12 1986

STATE CORPORATION COMMISSION

Signed James R. Kapp
(TECHNICIAN)

INV. NO. 12939

MAR 12 1986

CONSERVATION DIVISION
Wichita, Kansas