

To: ✓ 1 120824 9-17
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 093-21,293.0000
SE SE SE, SEC. 11, T 21 S, R 35 W/E
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4779
Operator: North American Resources Co.
Name: 16 E. Granite
Address: Butte, Montana 59701

Lease Name Crist Well # 11-1
County Kearny
Well Total Depth 2902 94.31 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Chief Drilling, Inc. License Number 5886
Address 120 S. Market, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 4:30 p.m. Day: 17 Month: 9 Year: 1993

Plugging proposal received from Harold Dinkle
(company name) Chief Drilling, Inc. (phone) 316-262-3791

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1991'

1st plug at 2000' with 50 sx cement, 2nd plug at 1000' with 50 sx cement,

3rd plug at 400' with 75 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:30 p.m. Day: 17 Month: 9 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 2000' with 50 sx cement,

2nd plug at 1000' with 50 sx cement,

3rd plug at 400' with 75 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

INVOICED

1 (XXXXX/ did not) observe this plugging.

DATE 10-1-93

INV. NO. 38817 9-17

Signed Duane Rankin
(TECHNICIAN) CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1993