

1080303

TO: STATE CORPORATION COMMISSION API NUMBER 15-093-21,656.0000
20'S 60'W E/2 SE SW SEC. 11, T 21 S, R 35 W

CONSERVATION DIVISION - PLUGGING SECTION 640 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3030 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BAILEY WELL # 1-11

TECHNICIAN'S PLUGGING REPORT 4/20 COUNTY KEARNY 162.50

OPERATOR LICENSE # 5210 WELL TOTAL DEPTH 5000 FEET

OPERATOR: LEBSACK OIL PRODUCTION PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 489 SURFACE CASING: SIZE 8 5/8" @ 236' WITH SX

ADDRESS HAYS, KS 67601-0489

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CHEYENNE DRILLING LICENSE NUMBER 5382

ADDRESS 3728 W JONES AVE, GARDEN CITY, KS 67846

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 20 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM PHIL LLOYD

(COMPANY NAME) CHEYENNE DRILLING (PHONE) 316-277-2062 RECEIVED STATE CORPORATION COMMISSION

WERE: APR 28 2000

1ST PLUG AT 3100' WITH 100 SX CEMENT. 2ND PLUG AT 2238' WITH 50 SX CEMENT.

3RD PLUG AT 1200' WITH 80 SX CEMENT. 4TH PLUG AT 250' WITH 40 SX CEMENT. CONSERVATION DIVISION Wichita, Kansas

5TH PLUG AT 0-40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 20 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 3100' WITH 100 SX CEMENT. 2ND PLUG AT 2238' WITH 50 SX CEMENT.

3RD PLUG AT 1200' WITH 80 SX CEMENT. 4TH PLUG AT 250' WITH 40 SX CEMENT.

5TH PLUG AT 0-40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) INVOICED DATE 5/1/00 062.54

I DID NOT OBSERVE THIS PLUGGING.

SIGNED Kevin D. Shult (TECHNICIAN) FORM CP-2/3