

1041132

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-097-20,373-0000  
C NE NE, SEC. 12, T 28 S, R 18 W/EX  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT *12-15*  
Operator License # 30606  
Operator: Murfin Drilling Co., Inc.  
Name & Address 250 N. Water, Ste. 300  
Wichita, KS 67202

Lease Name Einsel Well # 1  
County Kiowa *156,49*  
Well Total Depth 4815 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 443

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 15 Month: 12 Year: 1995

Plugging proposal received from Richard McIntyre  
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

Work: 5 1/2" at 4805', PRTD 4785', Perfs at 4741-54'  
1st plug pump 2 sx hulls and 25 sx cement to 4500'  
2nd plug pump spot 50 sx cement at 1160', 3rd plug spot 50 sx cement at 460'  
4th plug spot 10 sx cement at 40'. Gel spacer between plugs.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 a.m. Day: 15 Month: 12 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 100 lbs. hulls and 25 sx  
common cement. Stopped plug at 4500'

Spotted plugs through 5 1/2" casing with gel spacer between plugs:  
2nd plug at 1160' with 50 sx cement,  
3rd plug at 460' with 50 sx cement,  
4th plug at 40' with 10 sx cement.

RECEIVED  
KANSAS CORPORATION COMMISSION  
*12-20-95*  
DEC 20 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2131' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
DATE JAN 09 1996  
OBSERVE THIS PLUGGING.  
INV. NO. 44451

Signed Steve Pfeifer  
(TECHNICIAN)