

To: 1 051688 6-25
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
206 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,354 - 0000

NW NW NW, SEC. 12, T. 28 S, R. 18 W/E

4950 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Einsel C Well # 1

Operator: A.L. Abercrombie, Inc.

County Kiowa 155.35

Name & Address Rt. 1, Box 56

Well Total Depth 4780 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 453

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 8 a.m. Day: 25 Month: 6 Year: 19 93

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4475' w/260 sx cement, PBSD 4452', Perfs at 4330-34'

1st plug sand back to 4270' and dump 5 sx cement on top of sand through bailer,

2nd plug at 2700' with 35 sx cement, 3rd plug at 2000' with 20 sx cement,

4th plug at 1150' with 50 sx cement, 5th plug at 470' with 50 sx cement,

6th plug at 40' with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1:30 p.m. Day: 25 Month: 6 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug sanded back to 4270' and dumped 5 sx cement on top of sand through bailer,

Spotted plugs through casing:

2nd plug at 2700' with 35 sx cement,

3rd plug at 2000' with 20 sx cement,

4th plug at 1120' with 50 sx cement,

5th plug at 470' with 50 sx cement, 6th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

1 (old) ~~XXXXXX~~ observe this plugging.

DATE 7-9-93

INV. NO. 38078

Signed: Richard W. Lusey (TECHNICIAN)

6-29-93 RECEIVED STATE CORPORATION COMMISSION JUN 29 1993 CONSERVATION DIVISION Wichita, Kansas