

R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-00180-00-01  
Spot: NENESE Sec/Twnshp/Rge: 22-28S-18W  
2350 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: JOHNSON Well Number: 1 OWW  
County: KIOWA Total Vertical Depth: 3740 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 125 N. MARKET, STE 1075  
WICHITA, KS 67202

Conductor Pipe: Size feet: 8/21.55  
Surface Casing: Size 8.625 feet: 562  
Production: Size feet:  
Liner: Size feet:

Well Type: LH UIC Docket No: Date/Time to Plug: 12/09/2002 1:45 PM

Plug Co. License No.: 32970 Plug Co. Name: H-D OIL FIELD SERVICE, INC.

Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 580' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. NO RAT HOLE & MOUSE HOLE.

Plugging Proposal Received By: SCOTT ALBERG

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/09/2002 3:00 PM

KCC Agent: SCOTT ALBERG

Actual Plugging Report:

TOP OF FISH @ 2835'. JUNK IN HOLE: 6 COLLARS & 23 JOINTS OF TUBING. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 580' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. NO RAT HOLE OR MOUSE HOLE. GOOD CIRCULATION ON JOB.

RECEIVED  
DEC 12 2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
DEC 10 2002  
KCC Dodge City

Signed

*[Signature]*  
(TECHNICIAN)

INVOICED

DATE 12-13-02

NV. NO. 2003060938

Form *[Signature]*