

To: 1 041202
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
150 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- 097-20,217-0000
C SW NW, SEC. 34, T 28 S, R 18 W/E
3300 feet from S section line
4620 feet from E section line

8-19

Operator License # 3959
Operator: Siroky Oil Management
Name:
Address P.O. Box 464
Pratt, KS 67124

Lease Name Cook A Well # 1
County Kiowa 163.41
Well Total Depth 5028 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 4:45 p.m. Day: 19 Month: 8 Year: 19 96

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" at 3763' w/175 sx cement, PBTD 3716', Perfs at 3588-96'
1st plug sand back to 3535' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:15 p.m. Day: 19 Month: 8 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3535' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 1200 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

1. (If additional description is necessary, use BACK of this form.)
2. Observe this plugging.

DATE AUG 29 1996

INV. NO. 43682

Signed Stephen J. Quisenberry (TECHNICIAN)

STATE CORPORATION COMMISSION RECEIVED 8-22-96

AUG 29 1996