

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,921-0000 R

NE/4, Sec. 30, T 28 S, R 18 W/D

1980 feet from N/W section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7306

Lease Name Michael King Well # 1

Operator: Cinco Exploration Co. Etal
Name &
Address Box 3723
Victoria, Texas 77901

County Kiowa

Well Total Depth 5000 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 1/2" feet 492'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Leben Drilling Co License Number Tag 434
5888

Address 10550 Broadway, Ste 640, Wichita, Kans 67202

Company to plug at: Hour: 8:30 PM Day: 29 Month: 11 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Kenneth Spear

(company name) Leben Drilling Co. (phone) _____

were: 1st plug @ 1200' w/ 50 sbx cement. 2nd plug @ 560' w/ 50 sbx cement. 3rd plug on solid bridge @ 40' to 0' w/ 10 sbx cement. circulated 10 sbx cement in each the rat & mouse holes. Halliburton accomplished the plugging with 50/50 pass cement w/ 2% gell + 3% C.C. The hole was full of heavy mud when pumping the cement through drill pipe.

Signed Paul A. Luther
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:30 PM Day: 29 Month: 11 Year: 1982

ACTUAL PLUGGING REPORT This hole was plugged as orders given in above paragraphs.

RECEIVED
STATE CORPORATION COMMISSION

DEC 1 1982

Remarks: _____

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I ~~was~~ / did not) observe this plugging.

INVOICED

DATE 12-20-82
INV. NO. 1866-11

Signed Paul A. Luther
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82