

2-010146

5-19

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

15.159.04361.0000

API NUMBER: DRILLED 1944

NE SW SE, SECTION 4 TOWNSHIP 21 RANGE 6W

OPERATOR LICENSE # 5056 990 FEET FROM S SECTION LINE  
OPERATOR F.G. HOLL COMPANY LLC 1650 FEET FROM E SECTION LINE  
NAME & 6427 EAST KELLOGG  
ADDRESS WICHITA, KS 67207

LEASE NAME: FREEMAN #2  
COUNTY: RICE 112.78  
WELL TOTAL DEPTH: 3470' (3420')  
PIPE: \_\_\_\_\_  
SURFACE CASING: 8 5/8" @ 210'

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: PRATT WELL SERVICE INC

ADDRESS: P.O. BOX 847, PRATT, KS 67124 LICENSE: 5893

COMPANY TO PLUG AT: HOUR: 8:30 DAY: 19 MONTH: 5 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: THOM POOL

COMPANY NAME: F.G. HOLL COMPANY LLC PHONE: (316) 672-2531

WERE: SAND TO 3350' AND TOP WITH 5 SACKS OF CEMENT. PERFORATE AT 1000' AND SPOT 35 SACKS OF CEMENT. PERFORATE AT 650' AND SPOT 35 SACKS OF CEMENT. PERFORATE AT 260' AND CIRCULATE CEMENT TO SURFACE.

5 1/2" CASING AT 3429'

4 1/2" CASING AT 960'

PERFORATIONS AT 3400'- 3420'

PLUGGING PROPOSAL RECEIVED BY: DL & MW

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { \_\_\_\_\_ } PART { X } NONE { \_\_\_\_\_ }

COMPLETED: HOUR: 16:00 DAY: 19 MONTH: 5 YEAR: 1997

ACTUAL PLUGGING REPORT: TUBING STUCK AT 820'. PUMPED 10 SACKS OF CEMENT AT 3400'. BACKED TUBING (2 1/2") OFF AT 537'. PERFORATED PIPE AT 528' TO 532' WITH 8 SHOTS. CIRCULATED 250 SACKS OF CEMENT TO SURFACE. SHUT WELL IN SO CEMENT COULD SET UP. TOPPED WITH 15 SACKS OF CEMENT ON 2/50/97.

REMARKS: 60/40 POZ 4% GEL HALLIBURTON #219074

RECEIVED  
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson

MICHAEL R. WILSON

INVOICED

JUN 03 1997

DATE

JUN 06 1997

CONSERVATION DIVISION  
WICHITA, KS

INV. NO.

48233

FORM CP-2/3

REV. 3/90

5-19

JUL 22 1997

dw