

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20977-00-00
Spot: NESWNW Sec/Twnshp/Rge: 5-21S-6W
990 feet from N Section Line, 4290 feet from E Section Line
Lease/Unit Name: RENOLLET B Well Number: 1
County: RICE Total Vertical Depth: 3520 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

Production Casing Size: 5.5 feet: 3519 100 SX CMT #114 40
Surface Casing Size: 8.625 feet: 242 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2003 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-5783

Proposed Plugging Method: Sand to 3400' and 3 sacks; 1000' and 35 sacks; 600' and 35 sacks; 295' to 0'.
RECEIVED
KCC DISTRICT #2
JUN 30 2003
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/24/2003 5:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:
Sanded bottom to 3400' and 5 sacks of common. Shot 5-1/2" casing off at 1586'. Pulled to 1000' and pumped 35 sacks. Pulled to 600' and pumped 35 sacks. Pulled to 295' and circulate cement to surface.
RECEIVED
KANSAS CORPORATION COMMISSION
JUL 08 2003
CONSERVATION DIVISION
WICHITA, KS

Remarks: ACID TICKET # 6417 60/40 4%

Plugged through: CSG

District: 02 Signed Jack Luthi
(TECHNICIAN)

INVOICED
DATE 7-8-03
INV. NO. 2004060043