

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21429-00-00
Spot: S2S2NW Sec/Twnshp/Rge: 5-21S-6W
1980 feet from N Section Line, 3960 feet from E Section Line
Lease/Unit Name: RENOLLET B Well Number: 5
County: RICE Total Vertical Depth: 3545 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

Production Casing Size: 5.5 feet: 3544 150 SX CMT
Surface Casing Size: 8.625 feet: 210 200 SX CMT #115²¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2003 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL COMPANY Phone: (620) 786-5783

Proposed Plugging Method: Sand to 3400' and 5 sacks; 1000' and 35 sacks; 600' and 35 sacks; 260' to 0'.

RECEIVED
KCC DISTRICT #2
JUL 7 2003
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 06/25/2003 11:00 AM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3400' and 5 sacks. Shot 5-1/2" casing off at 2230'. Pulled to 1000' and pumped 35 sacks. Pulled to 600' and pumped 35 sacks. Pulled to 260' and circulated cement to surface.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 08 2003
CONSERVATION DIVISION
WICHITA, KS

Remarks: UNITED TICKET #4744 60/40 4%

Plugged through: CSG

District: 02

Signed Jack L Luthi
(TECHNICIAN)

INVOICED
DATE 7.8.03
INV. NO. 2004060043