

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21178-00-00  
Spot: SENENW Sec/Twnshp/Rge: 5-21S-6W  
4620 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: RENOLLET B Well Number: 3  
County: RICE Total Vertical Depth: 3525 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 9431 E CENTRAL, SUITE 100  
WICHITA, KS 67206

Production Casing Size: 4.5 feet: 3534 150 SX CMT #11456  
Surface Casing Size: 8.625 feet: 211 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/30/2003 1:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ROB LONG Company: F. G. HOLL COMPANY Phone: (620) 786-5783

Proposed  
Plugging  
Method:

Sand to 3400' and 5 sacks of common; 1000' and 35 sacks; 600' and 35 sacks; 260' and 0'.

RECEIVED  
KCC DISTRICT #2  
JUL 8 2003  
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI  
Date/Time Plugging Completed: 06/30/2003 5:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: JACK LUTHI

**Actual Plugging Report:**

Sanded bottom to 3400' and 4 sacks. Shoot 4-1/2" casing off at 2070'. Pulled to 1000' and pumped 35 sacks. Pulled to 600' and pumped 35 sacks. Pulled to 260' and circulated cement to surface.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 08 2003  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED TICKET #4745 60/40 4%

Plugged through: CSG

District: 02

Signed

Jack Luthi  
(TECHNICIAN)

INVOICED

DATE 7-8-03  
INV. NO. 2004060043