State of Kansas

JOHN ANDERSON, Jr. WILLIAM L. MITCHELL, ALVIN F. GRAUERHOLZ Commissioner HARRY G. WILES RAYMOND B. HARVEY ROBT. C. LONDERHOLM Gen. Counsel


Governor Chairman Commissioner Secretary



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water) 500 Insurance Bldg. 212 N. Market WICHITA, KANSAS 67202



NOV 1 1965

CONSERVATION DIVISION Wichita, Kansas

has this

J. P. Roberts Assistant Director 500 Insurance Building 212 North Market Wichita 2, Kansas

Dear	Sir							
Mr.	Sam Mu	urphy	0:	Vir	gin	ia Drill	ing Co.	
date	requested	permission	to	plug	the	following	described	we1

Mr. Murphy guarantees payment of the plugging fee. Operator's full Name: Virginia Drilling Company, Inc. Complete Address: 712 Brown Bldg., Wichita, Kansas Lease Name: Ahlgrim Well No. # 1 Location: SE NE NE . Sec. 29 Twp. 21 Rge. 12 (E) (W) W County Stafford Total Depth 3670' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Murphy was instructed to plug the well as follows: 279' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 260', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', bridge with hulls, and cement with 10 sacks to base

of cellar, Bridge and cement rat hole with 2 sacks.

Very truly yours, archie Elving