



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 23 1962

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Nov. 18, 1962

CONSERVATION DIVISION  
Wichita, Kansas

11-26-62

Dear Sir:

Mr. Robert Miller of Graves Drilling Co. has this date requested permission to plug the following described well:

Mr. Robert Miller guarantees payment of the plugging fee.

Operator's full Name: Graves Drilling Co.

Complete Address: Box 332 El Dorado, Kansas.

Lease Name: Fischer #2 E Well No. #2

Location: NW-SE-NW Sec. 17 Twp. 21S Rge. 13 (E) (W) X

County Stafford County. Total Depth 3682. Oil Well \_\_\_\_\_

Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X Lost Hole \_\_\_\_\_

Mr. Robert Miller was instructed to plug the well as follows:

332' of 8 5/8" surface pipe circulated with 318 sacks cement.  
Hole filled to 180' with heavy mud, 1/4 sack hulls, 1st cementing  
plug and 25 sacks cement. Hole filled to 40' with heavy mud,  
1/4 sack hulls, 2nd cementing plug and 10 sacks cement to base  
of cellar. Rat hole bridged and 2 sacks cement.

Very truly yours,

*Herman Gustus*  
Conservation Division Agent