

State of Kansas



15.145.30102.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Flake of Woodman-Iannitti has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Woodman Iannitti Drilling Co.

Complete Address: 706 Union National Bldg., Wichita, Kansas

Lease Name: Peters Well No. 1

Location: NW NW NW Sec. 20 Twp. 21 Rge. 16 (E)(W) X

County Pawnee Total Depth 3544' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Flake was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 350' and displace  
25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug 1/2 sc  
hulls and 10 sc cement to base of cellar. Plug rat hole with 5 sc cement.

Very truly yours,

Geo Messing  
Conservation Division Agent