

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 34 TWP. 21 RGE. 13w E/W
Location as in quarters or footage from lines:
NE SE NE

Lease Owner Petroleum Energy Inc
 Lease Name Hooper A #1 Well No. _____
 Office Address First Nat'l Bank Bldg. Suite 415, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 12/17/82
 Plugging completed 12/21/82
 Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation _____ Depth to top _____ bottom _____ T.D. 3688'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	271'	none
				5 1/2"	3685'	2565'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged bottom with sand to 3585' & 5 sacks cement. Shot pipe @ 2570'.
Pulled 65 joints. Plugged well with 15 sacks gel, 70 cement, 2 hulls,
15 gel, 70 cement, 10 gel, 1 hull, plug, & 100 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of December, 19 82

My Commission expires:



RECEIVED
STATE CORPORATION COMMISSION
NOTARY

DEC 30 1982

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

OPERATOR: Petroleum Energy, Inc. 710 ^{One} Twenty Bldg. Wichita, Ks. 67202
CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Hooper Well No. A #1

Sec. 34 T. 21 R. 13W Spot NE SE NE

County Stafford State Kansas Elevation _____

Casing Record:

Surface: 8 5/8 @ 271' with 250 Sxs 3% cc
2% gel

Production: 572 @ 3685 with 165 Sxs.

Type Well: Oil Total Depth 3688'

Drilling Commenced: 8-1-81 Drilling Completed 8-10-81

Formation	From	To	Tops	
Cellar	0	7	Arbuckle	3685
Shale, Lime	7	1895		
Lime	1895	2602		
Shale, Lime	2602	2836		
Lime, Shale	2836	3180		
Lime	3180	3688		

RECEIVED
STATE OIL AND GAS COMMISSION
NOV 18 1982
CONSERVATION DIVISION
Wichita, Kansas

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: _____

Electric Log _____ Type and Depths Covered _____

