

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.185.21454.0000

LEASE NAME Fischer

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 34 TWP. 21 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 6-6-97

Plugging Completed 6-11-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kansas Corporation Commission

ADDRESS 130 S. Market, Room 2078 Wichita, KS 67202

PHONE (316) 337-6200 OPERATORS LICENSE NO. 100

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3704'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	298'	none
				5 1/2	3703'	2012'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s. Sanded bottom to 3300'. Checked hole next day, sand had fallen. Sanded bottom again. Checked hole, top of sand at 2855'. Ran 5 sks cement on top of sand. Shot well at 2012', worked pipe free. Allied plugged well as follows: Mixed 300# hulls, 10 sks gel, 50 sks cement, 10 sks gel, 100# hulls. Released plug, mixed 125 sks cement. Max psi 500". Shut in 200#. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kansas Corporation Commission

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 13th day of June, 19 97

Jane Szysberg
Notary Public

My Commission Expires:

