


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 34 Twp. 21S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines. SW SE SE
Lease Owner Wayne Walcher
Lease Name Fischer Well No. 1
Office Address 809 Central Bldg., Wichita 2, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-30-64 19
Application for plugging filed 7-30-64 19
Application for plugging approved 7-30-64 19
Plugging commenced 7-30-64 19
Plugging completed 7-30-64 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3707' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 255' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 250' 1/2 sk. hulls & 25 sks. cement through drill pipe Plug @ 250'
Mud to 40' Plug 1/2 sk. hulls 10 sks. cement. 2 sacks in rathel

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 1964

My commission expires April 1, 1967

Ulanda Nichols
Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Wayne Walcher
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: FISCHER #1
 LOCATION: SW SE SE Sec. 34-21S-13W
 STAFFORD COUNTY, KANSAS
 COMMENCED: 7-23-64
 COMPLETED: 7-30-64

| | | |
|------|-------------|---|
| 0 | 95 | Sand & Clay |
| 95 | 165 | Sand & Gravel |
| 165 | 240 | Shale with Sand Streaks |
| 240 | 255 | Redbed & Shells |
| 255 | 727 | Redbed & Shale |
| 727 | 753 | Anhydrite |
| 753 | 1080 | Redbed & Shale |
| 1080 | 1520 | Shale & Shells |
| 1520 | 1665 | Shale & Lime |
| 1665 | 2325 | Lime & Shale |
| 2325 | 2700 | Shale & Lime |
| 2700 | 2870 | Lime & Shale |
| 2870 | 3582 | Lime |
| 3582 | 3648 | Chert |
| 3648 | 3695 | Chert & Shale |
| 3695 | 3703 | Lime |
| 3703 | 3707 | Arbuckle |
| | <u>3707</u> | <u>Rotary Total Depth - D. & A.</u> |

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 3 1964
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used surface casing @ 255' with 225 sacks Sunset with 2% Gel.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Fischer #1 well, located SW SE SE of Section 34, Township 21 South, Range 13 West, Stafford County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 31st day of July, 1964.

Ulanda Nichols
 Ulanda Nichols, Notary Public

My Commission Expires:
 April 1, 1967