


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 34 Twp. 21 Rge. 13 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE, NW, SW
Lease Owner Leo J. Dreiling Oil Co.
Lease Name Gates Well No. 9
Office Address Victoria, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 12-12- 19 61
Application for plugging approved _____ 19____
Plugging commenced 12-13 19 61
Plugging completed 12-17 19 61
Reason for abandonment of well or producing formation water

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Laokamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3765 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	291	none
				5 1/2	3764	2845'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well plugged back with sand to 3375' mix and dump 5 sx cement from 3375' to 3345', pulled 5 1/2" osg (2845') filled hole with mud to 291' set rock from 291' to 281' mixed and dumped 20 sx cem from 281' to 220' filled hole with mud from 220' to 35' set 5' rock bridge to 30' mixed and put in 10 sx cem filled to base of cellar (4 ft below ground level)

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co License No 2
Address Great Bend Kans.

STATE OF Kansas, COUNTY OF Ellis, ss.
Leo J. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo J. Dreiling

(Address) _____

SUBSCRIBED AND SWORN to before me this 3rd day of January, 1962

My commission expires August 14, 1965 Roman G. Zimmerman Notary Public.



L. J. DREILING and SONS, Inc.

15.185.1956.0000

VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Company
Victoria, Kansas

Sec. 34 Twp. 21 Rng. 13

Farm Gates No. 9

Location SE NW SW

Total Depth 3765'

County Stafford County, Kansas

Comm. 9-26-61 Comp. 10-8-61

Elevation: D. F. 1887'

Contractor L. J. DREILING & SONS, INC.
VICTORIA, KANSAS

G. R. 1885'

Casing Record
8 5/8" - - - - 288'
5 1/2" - - - - 3765'

Cement Record
160 sags cement

Production:
Arbuckle

Figures Indicate Bottom of Formations

0 - 50	Surface Clay & Sand
50 - 128	Sand & Shale
128 - 160	Sand & Shale
160 - 191	Shale & Shells
191 - 425	Shale & Red Rock
425 - 731	Red Rock
731 - 752	Anhydrite
752 - 1312	Shale & Shells
1312 - 1760	Shale & Lime
1760 - 1890	Lime & Shale
1890 - 2090	Shale & Lime
2090 - 2300	Shale
2300 - 2615	Shale
2615 - 2815	Shale
2815 - 2903	Shale & Broken Lime
2903 - 3004	Lime
3004 - 3100	Lime
3100 - 3185	Lime
3185 - 3293	Lime
3293 - 3385	Lime
3385 - 3495	Lime
3495 - 3573	Lime
3573 - 3625	Lime
3625 - 3701	Lime
3701 - 3703	Lime
3703 - 3736	Lime
3736 - 3765	Lime
3765	TD

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1962

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy of the log from the Daily Drilling Report on your Gates No. 9.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 19th day of October, 1961.

Roman Zimmerman
NOTARY PUBLIC

My Commission Expires: 8-14-65