

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County. Sec 34 Twp. 21S Rge. 13W (E) W (W)

Location as "NE/CNW/SW" or footage from lines: NW SW SE

Lease Owner: Herman Geo. Kaiser

Lease Name: Fischer Well No. 1

Office Address: 908 Palace Bldg. - Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole

Date well completed: March 23, 1955

Application for plugging filed: March 23, 1955

Application for plugging approved: March 23, 1955

Plugging commenced: March 23, 1955

Plugging completed: March 23, 1955

Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: M. A. Rives - Pratt, Kansas

Producing formation: Depth to top: Bottom: Total Depth of Well: 3711 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	282'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 275' with 20 sacks cement.  
Top plug set at 35' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Anschutz Drilling Co., Inc.  
Address: 709 Union National Bank Building

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
E. G. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. G. Koelling*  
709 Union National Bank Building  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of April, 1955

My commission expires July 28, 1958

*Charles M. Barlow*  
Notary Public.

24-2675-5 2-52-20M

**PLUGGING**  
FILE SEC 34 T 21 R 13W  
BOOK PAGE 106 LINE 35

APR 5 1955  
CONSERVATION DIVISION  
Wichita, Kansas

4-5-55

DRILLER'S LOG

Herman Geo. Kaiser  
 #1 Fischer  
 NW SW SE 34-21S-13W  
 Stafford County, Kansas

<u>TO</u>	<u>FROM</u>	
0	245	Surface Clay & Sand
245	282	Red Rock
282	725	Red Shale & Shells
725	752	Anhydrite
752	1030	Shale & Shells
1030	1550	Shale, Salt & Shells
1550	1805	Lime & Shale
1805	1895	Lime & Shale
1895	2000	Lime
2000	2270	Lime & Shale
2270	2450	Shale & Lime
2450	2680	Shale & Shells
2680	2770	Lime & Shale
2770	2910	Shale & Lime
2910	3140	Lime & Shale
3140	3195	Lime
3195	3310	Lime & Shale
3310	3322	Shale & Lime
3322	3340	Br. Lime
3340	3380	L. Lime
3380	3533	Lime
3533	3586	Lime & Shale
3586	3610	Shale, Lime, Chert
3610	3651	Viola
3651	3658	Shale & Sand
3658	3709	Shale & Lime
3709	3711	Lime
	3711	ROTARY TOTAL DEPTH

COMMENCED: 3-14-55  
 COMPLETED: 3-23-55

CASING RECORD:

Set 282' of 8 5/8" surface casing with 200 sacks cement.

D & A

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Fischer located NW SW SE of Section 34-21S-13W, Stafford County, Kansas.

ANSCHUTZ DRILLING CO., INC.

BY: *E. G. Koelling*  
 E. G. Koelling

Subscribed and sworn to before me this 25th day of March, 1955.

*Charlene Barbour*  
 Notary Public

My Commission Expires: July 28, 1958.

**PLUGGING**  
 FILE SEC 34 T 21 R 13W  
 BOOK PAGE 106 LINE 85