

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 34 Twp. 21 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner Morganstern & Spector

Lease Name Mc Coy Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 6/29/48 19

Application for plugging filed March 16, 1959 19

Application for plugging approved March 17, 1959 19


Plugging commenced 4/28/59 19

Plugging completed 5/1/59 19

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Broadfooting Pulling Co.

Producing formation Arbuckle Depth to top 3703 Bottom 3706 Total Depth of Well 3719 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"OD	259	None
				5 1/2"OD	3713'	2710'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set rock bridge at 200 feet- Dumped 20 sacks cement- Mudded hole to 40 feet and dumped 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1959

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E & L Casing Pulling Co.

Address 1416 Coolidge, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Morganstern & Spector (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Morganstern & Spector*

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 1959

My commission expires Dec 1, 1959

Notary Public.

PLUGGING  
FILE SEC 34 T. 21 R. 13  
BOOK PAGE 22 LINE 6

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

COPY

Company - LION OIL COMPANY  
Farm - McCoy No. 1

SEC. 34 T. 21S R. 13W  
NE NE NW

Total Depth. 3719'  
Comm. 6/17/48 Comp. 6/29/48  
Shot or Treated. 5000 acid  
Contractor. R.W. Rine Drilling Company  
Issued. 9/4/48

County. Stafford  
KANSAS



CASING: 8 5/8" @ 259'  
5 1/2" @ 3713'

Elevation. \_\_\_\_\_

Production. Est. Pmp 35 BOPD

Figures Indicate Bottom of Formations.

sand	230
shale & shells	259
red rock & sand	720
anhydrite	755
sand, shells & shale	1770
lime & shale	1870
shale & shells	1970
lime	2080
lime & shale	2430
shale	3010
lime & shale	3205
lime	3255
lime & shale	3515
lime	3600
lime & shale	3715
lime & shale	3719
total depth	
Tops:	
Lansing	3366
Viola	3626
Simpson	3663
Arbuckle	3706

RECEIVED  
STATE CORPORATION COMM.

MAR 16 1959

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 34 T 21 R 13W  
BOOK PAGE 22 LINE 6